

Name of work:- Providing foundation for the Installation of MIG 21 in A.E.D. At PEC Sector-12, Chd					
Sr. No.	Sub-Heads and item of work	Qty	Unit	Rate	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size).	0.27	cum		
2	Providing and laying in position specified grade of reinforced cement oncrete,excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size).	1.50	cum		
3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :				
	cement mortar 1:4 (1 cement : 4 coarse sand)	9.05	sqm		
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	300.00	kg		
5	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed. within a lead of 50 m.				
	All kinds of soil.	2.48	cum		
Total					