

Name of Work: P & F terra kota tile cladding on toe walls at new academic block at PEC**SCHEDULE OF QUANTITY**

Sr. No.	Description of items	Qty	Unit	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	90.00	sqm		
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	2.00	cum		
3	Providing and fixing wall lining facing as per approved sample work with average thickness(15mm to 18mm) 17mm to 20mm thick cladding tile face to size 230mmx70mm having 10mm deep and 10mm wide horizontal and vertical straight joint and to be fixed over brick/RCC wall, beam etc. with 12mm thick cement plaster 1:3(1 cement :3 coarse sand). The joints shall be properly recessed and finished. All joints shall be in straight line having 10mm wide groove in horizontal and vertical sides. The tiles in corner shall have recessed joint by overlapping one tile of one side over another tile from opposite of wall. The complete work shall be done as per architectural drawings complete in all respect to the entire satisfaction of engineer-in-charge.	90	sqm		
				Total	