

Punjab Engineering College, Sector-12, Chandigarh

(Deemed to be University)

No. PEC/EO/2021/ 984

Dated: 13 JAN 2022

Notice Inviting Quotations

Sealed Quotation are hereby invited on behalf of Director, Punjab Engineering College, Sector-12, Chandigarh on percentage rate basis for the following work and will be opened in the office of the undersigned on dated 18.01.2022 at 3:30 p.m. The quotations will be received on or before 18.01.2022 upto 3:00 p.m.

Name of Work : Providing Copper Plate earthing and copper wiring in Research Lab of Applied Sciences in Punjab Engineering College, Sector-12, Chandigarh.

Schedule of Work

SLNo	Description	Qty	Unit	Rate	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. Make Polycab, Havells, Finolex, L&T,RR Kables				
	2 x 4 sq. mm	60	Metre	86.00	5160
2	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. Make Diplast, Polyplast AKG, Polycab (ISI)				
	25 mm	30	Metre	90.00	2700
3	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required. (Earthing shall be done 15 feet deep for ground level)	1	Set	14442.00	14442
4	Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required.	12	Metre	1608.00	19296
5	Providing and fixing testing joint made of MS sheet box size 10"X8"X5", having 8" long copper strip 25mmX5mm fixed in the box on porcelain/bakelite insulators. The strip shall have 6 nos holes 5mm dia after equal distance. The box shall have openable hinged type door. The box shall be fixed on wall recessed on surface.	1	each	2000.00	2000
	Total				43598
	Rate to be quoted by the contractor				%Less/Above

Conditions:

- 1 The work shall be carried out according to CPWD General Specifications.
- 2 No claim on account of fluctuation in prices due to any reason shall be considered.
- 3 The quantity can be increased or decreased as per actual requirement at site.
- 4 No premium will be allowed on M.R. Items, abatement, if any shall be applicable on all items including market rates.
- 5 Any error or omission in nomenclature or unit can be corrected at any stage.
- 6 The quality of material shall be strictly in accordance with the specification given in DNIT.
- 7 All the material shall be inspected by the Engineer-in-charge before installation at site.
- 8 The department has reserve the right to issue any amendment to the work order as emergency demands or allow of altogether cancel the contract without assigning any reason. The Deptt. Reserves the right to delete any item.
- 9 Discount offered by the firm should also be considered in additional/ extra DSR/ MR Items, if the rate quoted are lesser than the DNIT amount.
- 10 The firm shall quote the rates inclusive all the taxes/ GST whatever required and no extra payment shall be made in this respect.

Endst. No.

984-86

Copy of the above is forwarded to the following:

1. Chairman Estate & Works
2. Webmaster, with a request to upload on the Institute website
3. Notice Board

University Engineer
Dated:

University Engineer