

Punjab Engineering College, Sector-12, Chandigarh

(Deemed to be University)

No. PEC/UE/2022/ 15809-11

Dated:

Notice Inviting Quotations

10 AUG 2022

Sealed Quotations are hereby invited by the undersigned on behalf of the Director, Punjab Engineering College, Sector-12, Chandigarh on percentage rate basis for the following work and will be opened in the office of the undersigned on dated 12.08.2022 at 3:30 P.M. The quotations will be received up to 3:00 P.M on 12.08.2022. The bidder must be enlisted with Chandigarh Administration in the relevant category.

Name of Work: Providing and fixing of temporary shed for mess kitchen and washing area of aravali hostel at Punjab Engineering College, Chandigarh.

SCHEDULE OF QUANTITIES

S. No.	Description of Items	Qty.	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
	All kinds of soil	2.5	cum	205.45	513.63
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	2.5	cum	7365.15	18412.88
3	1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	2.00	cum	6050.65	12101.30
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	220	kg	78.20	17204.00
5	Providing and fixing pre coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer- in-charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	50	sqm	671.55	33577.50

6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	Two or more coats on new work	7	sqm	131.45	920.15
	Total				82729.00
Rupees Eighty two thousand seven hundred twenty nine only					
Rate to be quoted by the bidder _____ % below/ Above					

Terms & Conditions:

1. The work shall be carried out as per CPWD specification and as per direction of the EIC.
2. No T&P shall be issued to the agency.
3. The necessary recoveries as applicable shall be made from the bill.
4. Time allowed 30 days.
5. Nothing extra shall be paid on any other account.

Endst. No. PEC/EO/ 15809-11

Copy of the above is forwarded to the following:

1. Chairman Estate & Works
2. Webmaster, to upload on institute website.
3. ☒ Notice Board


University Engineer

Dated

10 AUG 2022


University Engineer